

Site survey report

Proposed northern district hospital

Plot beside the regional health office · Survey date 14 August 2026

1. Summary

The 6.8 hectare plot is level, above the 100-year flood line and served by the regional road on its eastern boundary. No protected trees or heritage features were found. Ground conditions are suitable for two- and three-storey buildings on conventional foundations.

2. Access

The existing track from the regional road is 3 km long and unsurfaced. Upgrading it to a two-lane road with a footpath and a bus bay is required before Phase 1 construction traffic starts.

3. Utilities

A 33 kV line runs 400 m north of the plot. Mains water is available at the health office; a new 150 mm main and on-site storage for 48 hours of demand are recommended. There is no sewer connection, so an on-site treatment plant is needed.

4. Recommendations

1. Build the access road alongside Phase 1.
2. Reserve the northern third of the plot for Phase 2 wards.
3. Commission a detailed drainage design before tender.

Prepared for the Ministry of Health by the regional works department. Sample document for the Insight Pitch demo.